

		<p>Once you have tightened all hardware and reinstalled and torqued the wheels/tires, it is now necessary to adjust the torsion bar keys to the desired height, (not to exceed 2.25 in.). When adjusting the torsion keys, make sure to take pressure off of the suspension in order to avoid damaging the adjusting bolts. The vehicle will also need to be aligned and final adjustments may be required in order to properly align. Align vehicle to factory specs and be sure to readjust the headlamps as well.</p>
<p>Picture shows spacers being installed onto upper studs.</p>	<p>Reposition shock and tighten with new provided hardware.</p>	

Final Checks & Adjustments

Post Installation Warnings: Once the vehicle is lowered to the ground, check all parts which have rubber or urethane components to insure proper torque. Torque wheels to factory specs. Move vehicle backwards and forwards a short distance to allow suspension components to adjust. Turn the front wheels completely left then right and verify adequate tire, wheel, brake line, and ABS wire clearance. Test and inspect steering, brake and suspension components for tightness and proper operation. Inspect brakes hoses and ABS lines for adequate slack at full extension. Failure to perform the post inspection checks may result in vehicle component damage and/or personal injury or death to driver and/or passengers. Test drive vehicle and re-check the torque of all fasteners and re-torque wheels on vehicle.

Wheel Alignment/Headlamp Adjustment:

It is necessary to have a proper and professional wheel alignment performed by a certified alignment technician. Align the vehicle to factory specifications. It is recommended that your vehicle alignment be checked after any off-road driving. In addition to your vehicle alignment, for your safety and others, it is necessary to check and adjust your vehicle headlamps for proper aim and alignment.

Vehicle Re-Torque and Safety Inspection:

Upon completion of all services and adjustments performed on your vehicle, and within 50 miles of driving, check to ensure all fasteners and hardware are properly torqued to specification as noted in the vehicles factory service manual.